GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

R&B Dept –Usage of Hot Mix Plant of 100/120 TPH Batch Type within 100 Km distance of the site of work in the qualification criteria for all R&B works involving Dense Bituminous items of works - Orders – Issued.

TRANSPORT, ROADS & BUILDINGS (R.I) DEPARTMENT

G.O.Rt.No.180 Dated:19.06.2017

Read the following:

1. G.O.Rt.No.179, TR&B(R.I)Dept., dt.6.2.2014
2. From the ENC(R&B) Admn. & State Roads, Vijayawada Lr.No.9999/ DEE.5/AEE.2/1999, dts:15.11.2016, 20.12.2016,28.12.2016, 4.1.2017, 24.1.2017.
3. Representation of Builders' Association of India, dt.7.2.2017
4. From the ENC(R&B)Admn. & SR, Lr.No.9999/ DEE.5/AEE.2/ 1999, dt.23.02.2017 and 26.4.2017
5. From the Chief Engineer(R&B)MDR & LWE, Lr.No.9999 /DEE.5 /AEE.2 /1999, dt.15.6.2017

ORDER:

In the G.O.1st read above, orders were issued regarding owning of Hot Mix Plant within 70 Kms distance of the site of work site in the qualification criteria for all road works costing up to Rs.5.00 Crores, involving bituminous items of work and for works costing more than Rs.5.00 Crores, this condition should not be stipulated.

2. The Engineer-in–Chief(R&B)Admn.& SR / Chief Engineer (R&B)MDR & LWE in the references 2nd, 4th & 5th read above, have informed that the Committee of Chief Engineers of (R&B) Dept has recommended for the usage of Hot Mix Plant 100/120 TPH batch type in accordance with MoRTH specification for Roads & Bridge works involving Dense Bituminous Mixes like DBM, BC which require to close control over the proportioning of materials by weight. Further, the Builders Association has requested the location of the HMP from work site can be increased from the present 70 km to 100 km. The Chief Engineer(R&B) MDR & LWE, has requested to issue necessary orders for usage of Hot Mix Plant (Batch Type) 100/120 TPH for Road works duly supersession of G.O.1st read above.

3. In the aforesaid circumstances, in view of the recommendations of the Committee of Chief Engineers of R&B Dept, and in supersession of G.O.1st read above, after careful examination of the matter, Government, hereby impose the following conditions for all R&B works involving Dense Bituminous Mixes like DBM, BC as the qualification criteria:

i) The usage of Hot Mix plant of Batch Type of 100/120 TPH Capacity shall be made mandatory for all the Works wherever the works involve the provisions of Dense Bituminous Mixes such as DBM and BC, with immediate effect.

ii) The Hot Mix plant shall be located within a distance of 100 Km from the Work site, in order to have control over the temperature of the Bituminous Mixes. The Contractor shall procure the Hot Mix material to the work site duly maintaining and ensuring the required laying temperature, as per the specifications.

iii) For all the Works ***, irrespective of the cost***, the bidders may be permitted to either ***own or lease*** the said Batch type Hot Mix Plant of 100/120 TPH Capacity located within a distance of 100 Km from site of Work and produce the necessary Documents at the time of submission of bid, if the Work involves the component of DBM/BC.

(Contd…….2)

4. The Chief Engineer (R&B) MDR & LWE, A.P., shall take necessary further action in the matter accordingly.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

SUMITA DAWRA
PRINCIPAL SECRETARY TO GOVERNMENT

To
The Engineer-in-Chief (R&B) Admn., SH, MD, APRDC(I/C),
EAPs & CP Ibrahimpatnam, Vijayawada

The Engineer-in-Chief (R&B) N.H. (I/C), Ibrahimpatnam,Vijayawada

The Chief Engineer (R&B) NABARD , RDF & PPP, (I/C),
Ibrahimpatnam, Vijayawada

The Chief Engineer (R&B) MDRs & LWE, (I/C) Ibrahimpatnam, Vijayawada

The C.E(R&B) Buildings & RSW (I/C), Ibrahimpatnam, Vijayawada

The Chief Engineer, COT, Ibrahimpatnam,Vijayawada
copy to:
P.S. to Hon'ble M(R&B)
P.S. to Prl.Secretary, TR&B
Sf/Sc

// FORWARDED BY ORDER//

SECTION OFFICER